

PARISH PRESIDENT

JEFFERSON PARISH LOUISIANA

PURCHASING DEPARTMENT

Provide the services, leadership, and vision to improve the quality of life in Jefferson Parish."

PATRICIA W. LASSALLE PURCHASING DIRECTOR

December 1, 2009

ADDENDUM #2

RFP No. 0201

Proposal Receipt Date: January 13, 2010

Management Services for the Jefferson Performing Arts Center

CLARIFICATION TO THE SPECIFICATIONS:

- 1. Furniture and Fixtures: There is fixed seating in the building for the audience, but there is not any additional furniture. There is extensive theater lighting throughout the building, as well as the normal lighting that you would expect in any building.
- 2. Audio/ Visual System: This system is intended to include the following: Line arrays left and right of the proscenium, under balcony delay and side loud speaker systems, fully integrated 4 channel production intercom system, stage managers/default mixer and auxiliary equipment, listen through ceiling loudspeakers at the dressing room and back stage, and ancillary devices related to input, mixing, processing, microphones, jacks, wire, and amplification of audio into the system.
- 3. Floor plan: drawings of the general floor plan and the artist rendering included in the addendum.
- 4. Theatrical Props: This building has stage rigging that includes the following: Proscenium fire curtain and motorized lineshaft rigging, manual counterweight set for the house curtain, T-bar battery for total inventory of undedicated and manual counterweight sets spaced 6 inches on center, 1600 pound capacity single purchase and manual counterweight sets, upper and lower continuous lock rails, and associated index strip lights, 3 motorized counterweight sets, 30,000 pounds of steel counterweights for undedicated manual counterweight sets, 40 belaying pins, rope blocks, rope and cable cradle for stage lighting mulitconductor cable pick up, rope block for spotline rigging, motorized tracked variable acoustics curtains system, and stage draperies. Also included is an orchestra lift by Gala of Canada. This lift is a spiral lift system that is located immediately in front of the stage.
- 5. Telephone and office equipment is not included in the general contractor's scope of work.
- 6. Concession Area: There are rough-ins for a sanitary sewer drain and water service for the concession area at the lobby. However, there is not a concession "bar" or any build out for a concession area.

RFP 0201 Addendum 2 Page 2

DELETE:

Page number 20 titled "Attachment A" should be removed from the proposal.

PROPOSAL RECEIPT DATE WILL REMAIN THE SAME JANUARY 13, 2010.

THIS ADDENDUM FORMS A PART OF THE CONTRACT DOCUMENTS AND MODIFIES THE ORIGINAL RFP PROPOSAL DOCUMENTS AND SPECIFICATIONS. THE CONTENTS OF THIS ADDENDUM SHALL BE INCLUDED IN THE CONTRACT DOCUMENTS. CHANGES MADE BY THIS ADDENDUM SHALL TAKE PRECEDENCE OVER THE DOCUMENTS OF EARLIER DATE.


Sincerely,


Japhne Melson, Buyer II

Jefferson Purchasing Department

PLEASE ACKNOWLEDGE RECEIPT OF THIS ADDENDUM BY SIGNING AND RETURNING THIS ADDENDUM IN ITS ENTIRETY WITH THE RFP PROPOSAL

COMPANY NAME:	
SIGNATURE:	
DATE:	





RFP 0201 Page 5